

Township 3 North Range 35 East

Chains	North on East boundary of Section 25	
40.00	Set basalt stone 7x9x12 for $\frac{1}{4}$ Section Corner. Var. 20° E.	‡200
80.00	Set post corner for sections, 24, 25, 19 & 30, drove charred stake, dug pits and raised mound as per instructions.	‡250
	This line passes up hill side.	
	Lane stony, grass good.	
80.00	North on E. Bdy. of Sec. 24. Var. 21° East.	
80.00	Set basalt stone 9x16x18 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post cor. for Secs. 24, 13, 18 & 19 from which	
	A pine, 8 ins. diam. bears S 40° W. 28 lks.	
	A pine, 12 ins. diam. bears N. 42° W. 35 lks.	
	A pine, 6 ins. diam. bears N. 60° E. 8 lks.	
	A pine, 7 ins. diam. bears S. 70° E. 9 lks.	
	Land somewhat broken, good grass, soil 2nd rate.	
	Some scattering pine timber, this corner.	
	North on East Bdy. of Sec. 13. Var. 21° E.	
40.00	Set post $\frac{1}{4}$ Sec. cor. from which	
	A pine 7 ins. diam. bears N. 40° W. 75 chs.	
	no other tree near. Dug pits and raised mound as per instructions.	
70.00	Wild Horse Creek channel dry course N. W.	-250
80.00	Set post cor. for Secs. 12, 13, 7 & 18 from which	‡75
	A pine, 20 ins. diam. bears S. 55° W. 28 chs.	
	" " " " " " N. 75° W. 68 chs.	
	" " 24 " " " " N. 40° E. 42 chs.	
	" " " " " " South 40 chs.	
	Land broken, good grass soil 2nd rate, some good timber on hill side to the south of Wild Horse Creek.	
	July 28, 1856	
	North on E. Bdy. of Sec 12. Var. 21° East.	
40.00	Set post corner for $\frac{1}{4}$ Sec., drove charred stake, dug pits, and raised mound as per instructions.	‡75
76.00	Road to timber course E. & W.	‡50
80.00	Set post cor. for Secs. 1, 12, 6 & 7, drove charred stake, and raised mound as per instructions.	
	Land broken, good grass, soil 2nd rate	