

Township 3 North Range 35 East.

| | | |
|--------|--|------|
| Chains | North East Boundary of Section 1. Var. 20° East. | |
| 40.00 | Set post. corner for $\frac{1}{4}$ Sec. on side of hill facing west, dug pits and raised mound as per instructions. | |
| 66.00 | Pine Creek 8 lks. wide course, west. | |
| 80.00 | Set post corner for Township 3 & 4 North Ranges 35 & 36 E. Sections. 1, 6, 31 & 36. Mark stone mound as per instructions. | |
| | Land broken, good grass, some timber on south side of Pine Creek. | |
| | Surveyed by, William H. Odell. - Contract 114. | |
| | Field notes of the subdivision lines of Township No. 3 North of the Base line of Range 35 East of Willamette Meridian. | |
| | The Umatilla Indian Reservation embraces the greater part of this Township hence I survey only that portion not so embraced excepting so much as may be necessary to complete in a rectangular form such sections as may be situated in part only on said reservation. | |
| | Wildhorse Creek being the only boundary on the north of said reservation. | |
| | Therefore I commence at post corner for sections 13, 24, 18 & 19 on East Boundary, Thence West between Secs. 13 & 24. | |
| 40.00 | Set basalt stone 7x9x12 cor. for $\frac{1}{4}$ Sec. | |
| 62.50 | Bottom of deep ravine course south | -300 |
| 80.00 | Set post corner for Secs. 13, 14, 23 & 24, drove charred stake, dug pits, and raised mound as per instructions. | |
| | Land broken good grass, soil 2nd rate. | |
| | North between Secs. 13 & 14. Var. 20° 30' East. | |
| 30.25 | Road course East and West. | |
| 40.00 | Set post corner for $\frac{1}{4}$ Sec., drove charred stake, dug pits and raised mound as per instructions. | |
| 76.00 | Wildhorse Creek, channel dry course W. | -200 |
| 80.00 | Set post corner Secs. 11, 12, 13 & 14, drove charred stake, dug pits and raised mound as per instructions. | |
| | Land broken, some fir and pine timber on hill side south of creek Soil 2nd rate. | |
| | East on random between Secs. 12 & 13. Var. 21° East | |