

Township 3 North Range 35 East W. M.

Chains		
40.00	Set temp $\frac{1}{4}$ Sec. cor.	
79.87	Intersected N. & S. line 39 lks. N. of post cor. N. $89^{\circ} 42'$ W. on true line.	
24.50	Wildhorse Creek course N. 80° W. channel dry.	-75
39.95	Set post cor. for $\frac{1}{4}$ Sec. drove charred stake, dug pits and raised mound as per instructions.	
41.75	Wildhorse Creek course S. 80° W.	
79.81	To post corner. Land broken, scattering timber, fir and pine. Soil 2nd rate.	
<hr/>		
	North bet. Secs. 11 & 12.	
30.00	Summit of hill	+ 250
40.00	Set post cor. for $\frac{1}{4}$ Sec. drove charred stake, dug pits, and raised mound as per instructions.	
55.12	Bottom of ravine course W.	-100
65.00	Summit of hill	+100
80.00	Set post cor. for Secs. 1, 2, 11 & 12, drove charred stake, dug pits, and raised mound as per instructions, from which cor. A pine, 9 ins. diam., bears N. 6° E., 125 lks. A pine. 18 ins. diam., bears S. 70° E., 55 lks. Land hilly and stony, good grass.	
<hr/>		
	East on random between Secs. 1 and 12 Va. 21° East.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner	
80.15	Intersect N. & S line 56 links. North of post cor. W. $89^{\circ} 36'$ on true line.	
40.07	Set post cor. $\frac{1}{4}$ Sec., drove charred stake, dug pits, and raised mound as per instructions.	+30
80.15	To post corner. Land hilly, good grass, soil 2nd rate.	-80