

Township 3 North Range 35 East W. M.

| Chains | Field notes of the Survey of the Subdivision Lines of Township No. 3 North Range No. 35 East by Zenas F. Moody under Contract No. 164, bearing date. October 4th, 1871. |
|--------|--|
| | North bet. Secs. 35 & 36. |
| 40.00 | Set stone 18x14x9 for $\frac{1}{4}$ Sec. cor. |
| 55.00 | Old road very dim. |
| 64.30 | Umatilla River 125 lks. W. |
| 80.00 | Set post and made stone mound for cor. to Secs. 35, 36, 25, & 26. |
| | Land broken, soil good 2nd rate, very good grass. |
| | East on random bet. 25 & 36 |
| | Var. 21° E. |
| 40.00 | Set temporary $\frac{1}{4}$ S. cor. |
| 79.50 | Intersect N. & S. line 16 chs. S. of cor. S 89°53'W. on true line. |
| 39.75 | Set post and made stone mound for $\frac{1}{4}$ Sec. cor. |
| 79.50 | To corner. |
| | Land rolling, soil stony, very good grass. |
| | North bet. Secs. 25 & 26. |
| 40.00 | Set stone 18x10x7 for $\frac{1}{4}$ Sec. cor. |
| 80.00 | Set post and made mound of earth for cor. to Secs. 25, 26, 23 & 24. |
| | Land in tables, soil good, 1st rate, grass. |
| | East on random bet. Secs. 24 & 25. |
| | Var. 20° 30' E. |
| 40.00 | Set temporary $\frac{1}{4}$ Sec. cor. |
| 80.12 | Intersect N. & S. line 14 lks. N. of cor. N. 89°54' W. on true line. |
| 40.00 | Set stone 17x16x14 for $\frac{1}{4}$ S. cor. |
| 80.12 | To cor. S. |
| | Land level, soil 1st rate. |