

Township 3 North Range 35 East of W. M.

Chains	East bet. Sec. 11 & 14. Var. 20° 30' E.
40.00	Set post and made mound of earth for 1/4 Sec. cor.
72.00	To Wolf Horse Creek Boundary of Reservation. Land wild, soil good, 2nd rate, good grass.
<hr/>	
	North bet. Secs. 10 & 11. Var. 21° E.
40.00	Set post and mound of earth for 1/4 Sec. cor.
80.00	Set post and made mound of stone for cor. to Secs. 10, 11, 2 & 3. This cor. is on the bank of Wild Horse Creek the northern Bdy of Reservation. Land hilly, good grass. Oct. 19, 1871.
<hr/>	
	North bet. Secs. 33 & 34.
40.00	Set stone 17x15x8 for 1/4 sec. cor.
80.00	Set stone 18x14x9 for cor. to secs. 33, 34, 27, 28. Land hilly, soil 2nd rate, good grass.
<hr/>	
	East on random bet. secs. 27 & 34 Var. 21° E.
40.00	Set temp. 1/4 Sec cor.
79.84	Intersected N. & S. line 21 lks. S. of cor. S. 89° 51' W. on true line.
39.92	Set stone 18x14x12 for 1/4 S. cor.
79.84	To corner. Land rolling, soil 2nd rate, good grass.
<hr/>	
	North bet. Secs. 27 & 28.
40.00	Set stone 18x10x9 for 1/4 S. cor.
80.00	Set stone 20x12x7 for cor. to Secs. 27, 28, 21, 22. Land generally level, soil good, 1st rate, grass.
<hr/>	