

Township 3 North Range 35 East of W. M.

Chains.	<p>East on random line bet. Secs. 22 & 27. Var. 20° 30' E.</p>
40.00	Set temporary 1/4 Sec. cor.
79.80	<p>Intersected N. & S. line 14 lks. N. of corner. N. 89° 54' W. on true line.</p>
39.90	Set stone 17x14x7 for 1/4 sec. corner.
79.80	<p>To corner. Land rolling, soil good, good grass.</p>
North bet. Secs. 21 & 22.	
40.00	Set stone 17x14x9 for 1/4 S. cor.
80.00	<p>Set post and made mound of earth for cor. to secs. 21, 22, 15 & 16. Land level, soil 1st rate, good grass.</p>
<p>East on random bet. Secs. 15 & 22. V. 20° 30' E.</p>	
40.00	Set temporary 1/4 sec. corner.
79.64	<p>Intersected N. & S. line 12 lks. S. of cor. S. 89° 55' W. on true line.</p>
39.82	Set post and made earth mound for 1/4 S. cor.
79.64	<p>To corner. Land level, soil 1st rate, good grass.</p>
North bet. secs. 15 & 16.	
40.00	Set post and made earth mound for 1/4 S. cor.
80.00	<p>Set stone 18x12x9 for cor. to secs. 15, 16, 9, 10. Land rolling, soil 1st rate, good grass.</p>
<p>East on random bet. Secs. 10 & 15. Var. 21° E.</p>	
40.00	Set temporary 1/4 S. cor.
80.00	<p>Intersected N. & S. line 14 lks. N. of cor. N. 89° 54' W. on true line.</p>
40.00	Set post and made earth mound for 1/4 sec. corner.