

Township 3 North Range 35 East of the W. M.

Chains			
59.00	Spring Branch, 4 lks. flows S. W.		150
59.65	Road N. & S.		
80.14	To corner. Land rolling, soil 2nd rate, good grass.		
<hr/>			
	North bet. Secs. 28 & 29.		
40.00	Set stone 17x14x12 for $\frac{1}{4}$ S. cor.		
78.00	Wagon road course N. W. & S. E.		
80.00	Set stone 18x14x9 for cor. to Secs. 28, 29, 20, 21. Land level, soil 1st. rate, good grass.		
<hr/>			
	East on random bet. Secs. 21 & 28.		
		V. 21° E.	
40.00	Set temporary $\frac{1}{4}$ Sec. cor.		
79.64	Intersected N. & S. line 21 lks. S. of cor. S. 89° 57' W. on true line		
39.82	Set stone 18x12x9 for $\frac{1}{4}$ S. cor.		
79.64	To corner. Land generally rolling, soil 1st. rate, good grass		
<hr/>			
	North bet. 20 & 21.		
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. cor.		
80.00	Set post and made mound of earth for cor. Secs. 20, 21, 16 & 17 Land rolling, soil 1st rate, good grass.		
<hr/>			
	East on random bet. Secs. 16 & 21.		
		V. 21° E.	
40.00	Set temporary $\frac{1}{4}$ S. cor.		
80.00	Intersected N. & S. line 12 lks. N. of cor. N. 89° 55' W. on true line.		
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. cor.		
71.00	Spring bears south 10 chs.		
80.00	To corner Land rolling, soil 1st rate		