

Township 3 North Range 35 East of the W. M.

Chains	North bet. Secs. 16 & 17
40.00	Set stone 18x17x10 for $\frac{1}{4}$ S. cor.
80.00	Set post and earth mound for cor. to Secs. 16, 17, 8 & 9 Land level, soil 1st rate, good grass.
	East on random bet. Secs. 9 & 16 Var. 20° 30' E.
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
79.84	Intersected N. & S. line at cor. West on true line
39.92	Set post and made earth mound for $\frac{1}{4}$ Sec. cor.
79.84	To Corner Land level, Soil 1st rate. Good Grass.
	North bet. Secs. 8 & 9.
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. cor.
80.00	Set post and made earth mound for cor. to Secs, 8, 9, 4 & 5. Land sloping north, Soil 1st rate. Good Grass.
	East on random bet. Secs. 4 & 9. V. 20° 30' E.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.90	Intersected N. & S. line 14 lks. S. of cor. S. 89° 54' W. on true line.
33.40	Spring Branch flows North.
39.95	Set post and made earth mound for $\frac{1}{4}$ Sec. cor.
79.90	To corner. Land rolling, soil good, 2nd rate, good grass.
	North on random bet. Secs. 4 & 5.
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
80.24	Intersected North Boundary 64 lks. W. of cor. S. 00° 27' W. on true line.
40.24	Set post and made mound of earth for $\frac{1}{4}$ Sec. cor.
80.24	To corner. Land rolling, soil 1st rate, Good grass. Oct. 21, 1871.
	North bet. Secs. 31 & 32.
40.00	Set stone, 12x12x9 for $\frac{1}{4}$ Sec. cor.
80.00	Set post and made earth mound for cor. to Secs, 31, 32, 29 & 30 Land rolling, soil good 2nd rate, good grass.
	East on random bet. Secs. 29 & 32 V. 21° E.
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
80.14	Intersected N. & S. line 12 lks. S. of cor. S. 89° 55' W. on true line.