

Township 3 North Range 35 East of the W. M.

Chains	West on random bet. Secs. 6 & 7
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
79.84	Intersected N. & S. line 14 lks. N. of cor. N. $89^{\circ} 54'$ E. on true line.
39.84	Set post and made earth mound for $\frac{1}{4}$ Sec. cor.
47.84	To corner. Land rolling, soil good.
	North on random Secs. 5 & 6
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
80.35	Intersected North Boundary at cor. south on true line.
40.35	Set post and made earth mound for $\frac{1}{4}$ S. cor.
80.35	To corner. Land rolling, soil good.
	Oct. 23, 1871.
	Survey of the Subdivisional Lines of Township 3 North Range 36 E. Willamette Meridan, Oregon, by George L. Pershin U.S. Deputy Surveyor, under his contract No. 305 dated Sept. 20, 1878.
	I also begin at the corner to Secs. 7 & 18 on the west boundary of the Township and run and measure south.
18.15	To the channel of Wild Horse Creek, thence
17.50	To the 39th mile post the first one east of the west boundary S. $32\frac{1}{2}^{\circ}$ E. 500 chs.
	October 22, 1878.
	The stone used to set or mark corners are all Furuginious Basalt and very hard.
	Survey of the Exterior Lines of Township 4 North 35 E. Willamette Meridan, Oregon, surveyed by Jas. P. Currin and Jamed E. Noland, U.S. Deputy Surveyor under their special contract dated May 4, 1887.