

Exteriors of Township 4 North 35 East

	<p>East on random bet. Tps. 3 & 4 N. R. 35 E. Va. $19^{\circ} 30'$ E.</p> <p>I set temporary half mile & mile cors. at each 40 & 80 chs. and at 2 miles and 77.20 chs. Intersect E. line 210 lks. south of cor. to Secs. 3 & 4 T. 4 N R 35 E. Thence I run S. $89^{\circ} 30'$ W. on true line bet. Secs. 4 & 33. Var. 20° E.</p>
70.70	<p>Intersect U. R. bdy. and Wild Horse Creek, Set a post 48x4x4 ins. 12 ins, in the ground for closing cor. to Secs. 4 & 33. Marked U. R. C. C. on W. face, from which</p> <p> An alder, 8 ins. diam., bears S. 70° W. dist., 20 lks. marked U R C C B T.</p> <p> A willow 10 ins. diam., bears N. 75° W. dist., 62 lks. marked U R C C B T.</p>
80.00	<p>Set post 48x4x4 ins. 12 ins. in the ground for cor. to Secs. 4, 5, 32 & 33. Marked T 4 N. S. 33 on N. U.R. 35, E. S. 4</p> <p> S. E. T 3 N. S. 5 on S. W., S 32 on N. W., with 4 notches on E., & 2 notches on W. edges, Dug pits 18x18 x12 ins. in each Sec. $5\frac{1}{2}$ ft. dist. raised a mound of earth 2 ft. high $4\frac{1}{2}$ ft. base around post.</p> <p>Land level, soil 1st rate, some grass.</p>
20.00	<p>South $89^{\circ} 30'$ W. on true line bet. Secs. 5 & 32. Var. 20° E.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 cor. dug pits 18x18x12 ins. E. & W. of cor. $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ins. sq. 2 ft. long 12 ins. in the ground marked 1/16 S. of N. face.</p>
40.00	<p>Set a post 36x3x3 ins. 12 ins. in the ground for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ S. on N. face. Dug pits 18x18x12 E. & W. of cor. $5\frac{1}{2}$ ft. dist. I raised a mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base around post. on edges, dug pits</p>