

27

Exteriors of Township 4 North 35 East

Chains 60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor dug pits 18x18x12 ins. E. & W. of cor. 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it.</p> <p>In E. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.</p>
80.00	<p>Set post 48x4x4 ins. 12 ins. in the ground for cor. Secs. 5, 6, 31 & 32. Marked T 4 N S. 32 on N.E., R 35 E., S 5 on S. E., T 3 N S. 6 On S. W., S. 31 on N. W. with 5 notches on E. and 1 notch on W. edges. Dug pits 18x18x12 ins. in each Sec. 5½ ft. dist. raised mound of earth 2 ft. high 4½ ft. base around post.</p> <p>Land level, soil 1st rate, some grass.</p>
	<p>S 89° 30' W. on true line bet. Secs. 6 & 31.</p> <p style="text-align: right;">Var. 21° E.</p>
8.00	Wagon Road course N. & S.
11.50	Wagon Road course N. W. & S. E.
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. dug pits 18x18x12 E. & W. of cor. 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. Face.</p>
30.00	South Wagon Road.
40.00	<p>Set a post 36x3x3 ins. 12 ins. in the ground for ¼ Sec. cor. marked ¼ S. on N. face. Dug pits 18x18x12 ins. E. and W. of cor. 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base around post.</p>
60.00	<p>Deposited charred stake, 12 ins. in the ground for 1/16 Sec. cor. dug pits 18x18x12 in E. & W. of cor. 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it. In the E. pit drove stake, 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.</p>
61.50	Wagon Road course N. E.
72.00	Wagon Road course N. & S.