

23
Exteriors of Township 3 North 35 East

Chains 40.00	<p>Set a basalt stone, 9x8x7 ins. 6 ins. in the ground for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ on W. face, from which</p> <p>A pine 24 ins. in diam., bears N. 50° E. dist. 22 lks. marked $\frac{1}{4}$ S B T.</p> <p>A pine 16 ins. in diam., bears S. 83° W. dist., 30 lks marked $\frac{1}{4}$ S B T.</p> <p>Leave timber.</p>	400
49.50	Wagon Road Course E. & W.	
77.30	Gulch course W.	-20
80.00	<p>Set a post 4x4x4 ins. 24 ins. in the ground for cor. to Secs. 13, 18, 19 & 24, marked T 3 N, S 13 on N. W., R. 36 E., S. 18 on N. E. S. 19 on S. E., R. 36 E., S. 24 on S. W. with 3 notches on N. & S. edges, from which</p> <p>A pine 18 ins. in diam. bears N. 8° E. dist. 59 lks. marked T 3 N R 36 E., S 18 B T.</p> <p>A pine 36 ins. in diam bears S 65° W. dist. 122 lks marked R 35 E., S. 24 B T.</p> <p>No other trees in limits, dug pits 18x18x12 ins. Secs. 13, & 19, 5$\frac{1}{2}$ ft. dist. raised earth mound along side.</p> <p>Land mountainous.</p> <p>Soil rocky on 1st. $\frac{1}{2}$ rest good. 4th & 1st rate.</p> <p>Heavy pine timber on 1st. $\frac{1}{2}$ mile, good grass on balance.</p> <p style="text-align: right;">80.00 chs.</p>	
	<p>South bet. 19 & 24.</p> <p style="text-align: center;">Var. 18° 45' E.</p>	
40.00	<p>Set a basalt stone 12x10x8 ins. 8 ins. in the ground for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ on W. face, dug pits 18x18x12 ins. N. & S. of cor. 5$\frac{1}{2}$ ft. dist. & raised a mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base along side.</p>	
52.50	Draw course W.	-70
80.00	<p>Set a basalt stone 12x10x8 8 ins. in the ground for cor. to Secs. 19, 24, 25 & 30, marked 4 notches on N. and 2 notches on S. edges. Dug pits 18x18x12 ins. in each Sec. 5$\frac{1}{2}$ ft. dist. & raised mound of earth 3 ft. high</p>	