

## Exteriors of Township 3 North 35 East.

Chains	<p>Marked 6 notches on N. E. &amp; W. edges raised a mound of stone alongside</p> <p>Land Mountainous. 80.00 chs.</p> <p>Soil, rocky 4th rate.</p> <p>Pine &amp; balm timber in bottom.</p>	+250
	<p>General Description</p> <p>This township is rolling, soil a rich black loam. A large part of it in cultivation.</p> <p>Cottonwood &amp; willow along Umatilla River, which runs through the south part of township.</p> <p>Good grass in the S. &amp; E. portion.</p> <p style="text-align: right;">Aug. 24, 1887.</p>	
	<p>Survey of the subdivisonal Lines of Township 3 North Range 35 East Willamette Meridan, Oregon, as surveyed by Jas. P. Currin and Jas. E. Noland U.S. Deputy Surveyor, under their special contract dated May 4, 1887.</p> <p>Survey commenced, August 25, 1887.</p> <p>Survey completed, August 27, 1887.</p>	
	<p>Survey commenced with a Burt Improved Solar Compass.</p> <p>Beginning at old cor. to Sec. 11, 12, 13, 14. found old post rotted down with remnants in the ground. Restablished cor. Set stone 12x10x8 ins. 8 ins. in the ground. 4 notches on S. &amp; 1 on E. Dug pits 18x18x12 ins. in each Sec. 5 1/2 ft. dist. and raised a mound of earth 2 ft. high with 4 1/2 ft. base over stone. Thence East on random bet. 12 &amp; 13.</p> <p style="text-align: center;">Var. 22° East.</p>	
40.00	Set temp. 1/4 Sec. cor.	
83.92	Intersect Township line 20 lks. N. of cor. 12, 13, 7 & 18. Thence N. 89° 52' W. on true line.	
10.50	Canon Course S. W.	-100
17.00	Summit of ridge course S. W.	+50
24.72	To Wild Horse Creek, course N. E. & N. W. U.R. & D.R. bdy.	