

Subdivisions of Township 3 North Range 35 East.

Chains		
	<p>Set a stone 14x10x10 ins. 10 ins. in the ground for U.R. Meander and D. R. closing cor., marked U. R. M. C. on East face and D. R. on W. face and raised a mound of stone 2 ft. high with 4<math>\frac{1}{2}</math> ft. base alongside.</p> <p>Pits impracticable.</p>	
34.50	Wagon Road course N. & E.	+50
41.96	<p>Set post 3 ft. long 3 ins. sq. 24 ins. in the ground for <math>\frac{1}{4}</math> Sec. cor., marked <math>\frac{1}{4}</math> S. on N. face and raised a mound of stone, 1<math>\frac{1}{2}</math> ft. high with 3<math>\frac{1}{2}</math> ft. base alongside.</p> <p>Pits impracticable.</p>	
45.10	<p>Wild Horse Creek Course S. W. and U.R. and D.R. bdy. Set a stone <del>12x10x8</del> 8 ins. in the ground for U.R.M.C. on East and D.R. on S. faces. Around which I raised mound of stone.</p> <p>Pits impracticable.</p>	
49.37	<p>Wild Horse Creek Course S. W. and U. R. and D. R. bdy.</p> <p>Set a stone 18x9x8 ins. 12 ins. in the ground for U.R.M.C. Cor. and D. R. marked U.R.M.C. on W. and D.R. on S. faces. and raised a mound of stone 2 ft, high with 4<math>\frac{1}{2}</math> ft. base over it.</p>	
50.97	<p>Wild horse Creek Course S. W.</p> <p>Set stone 12x10x8 8 ins. in the ground for U.R. and D.R. Cors. Marked U.R.M.C. on E. and D. R. on S. faces and raised a mound of stone alongside. Pits impracticable.</p>	
83.92	<p>To corner to Secs. 11, 12, 13 &amp; 14.</p> <p>Land broken, some pine &amp; fir timber.</p> <p>Soil 3rd rate.</p>	
	<p>South on true line bet. Sec 13 &amp; 14.</p> <p style="text-align: right;">Var. 22° East.</p>	
2.00	<p>Wild Horse Creek Course S. W. and U. R. bdy.</p> <p>Set stone 12x10x8 8 ins. in the ground for U.R. bdy. and Meander Corner to fractional. Secs. 13 &amp; 14 marked U.R.M.C. on S. face around which I raised mound of stone.</p> <p>Pits impracticable.</p>	-25