

Subdivisions of Township 3 North Range 35 East.

| | | |
|---------|---|------|
| Chains. | | |
| 2.50 | Wagon Road course E. & W. | |
| 6.50 | Canon Course N. E. Enter Timber. | †30 |
| 20.00 | Set a post 3 ft. long 3 ins. sq. 24 ins. in the ground for 1/16 Sec cor. marked 1/16 S. on W. face from which A pine 30 ins. diam. bears S. 4° E. 57 lks. dist. marked 1/16 S B T. A pine 36 ins. diam. bears N. 85° W. 45 lks. dist. marked 1/16 S B T. Leave timber. | †100 |
| 40.00 | Set a stone 12x8x6 ins, 8 ins. in the ground for 1/4 Sec. cor. marked with 1/4 on W. face, and dug pits 18x18x12 ins. E. & W., from stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high with 3 1/2 ft. base over it. | |
| 47.50 | Wagon Road Course E. & W. | |
| 58.50 | Wagon Road Course E. & W. | |
| 60.00 | Set a stone 10x8x7 ins. 7 ins in the ground for 1/16 Sec. Cor., marked 1/16 on W. face. Dug pits 18x18x12 ins. N. and S. from stone, 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high with 3 1/2 ft. base alongside. | †400 |
| 80.00 | Set a stone 10x8x7 7 ins, in the ground for Cor. to Secs. 13, 14, 23 & 24. Marked with 3 notches on S. and 1 notch on East edges. Dug pits 18x18x12 ins. in each Sec. 5 1/2 ft. dist, and raised a mound of earth 2 ft. high with 4 1/2 ft. base over stone. Land rolling, and mountainous. 20.00 chs. 60.00 chs. Soil 1st class, Except Sec. 23 Good bunch grass. | |
| | East on random bet. Sec. 13 & 24. Var. 20° East. | |
| 40.00 | Set temp. 1/4 Sec. cor. | |
| 83.25 | Intersect East bdy. at cor. to Secs. 18, 19, 13 & 24. Thence W. on true line. | |
| 41.62 | Set a stone 12x8x7 ins. 8 ins in the ground for 1/4 Sec. Cor. marked 1/4 on N. face. Dug pits 18x18x12 ins. E. & W. from stone. 5 1/2 Ft. dist | |