

Subdivisions of Township 3 North Range 35 East

Chains 41.80	Set a stone 12x10x 8 ins. 8 ins. in the ground for $\frac{1}{4}$ Sec. cor. Marked $\frac{1}{4}$ on N. face, and raised a mound of stone over it. Pits impracticable  Ascend	
60.00	Gulch Course N. W.	-100
79.00	Canon Water in holes S.	-300
83.60	To corner to Secs. 23, 24, 25 & 26.  Land rolling on East $\frac{1}{2}$ and broken and mountainous. 40.00 chs. on West.  Bunch Grass Good.  Soil 1st and 3rd rate.	
South on true line Bet. Secs. 25 & 26.  Va. 23° East..		
1.90	Draw on ravine course east.	-30
11.00	Canon Course S. 20° W.	-400
40.00	Set a stone 12x10x4 ins. 8 ins. in the ground for $\frac{1}{4}$ Sec. cor. Marked $\frac{1}{4}$ on W. face. Dug pits 18x18x12 ins. N. and S. from stone, 5 $\frac{1}{2}$ ft. dist. and raised a mound of earth 1 $\frac{1}{2}$ ft. high with 3 $\frac{1}{2}$ ft. base alongside.	
72.00	Summit of point course S. W.	+50
80.00	Set a stone 12x10x8 ins. 8 ins. in the ground for cor. to Secs. 25, 26, 35 & 36. And raised a mound of stone over cor. Pits impracticable.  Land mountainous. 80.00 chs.  No timber, bunch grass.  Soil 2nd rate.	
East on random bet. Secs 25 & 36  Va. 20° 45' East.		
40.00	Set temp. $\frac{1}{4}$ Sec. cor.	
83.50	Intersect Township line at cor. to Secs. 30, 31, 25 & 26. Thence W. on true line.	
7.40	Gulch Course South	-100
12.50	Summit of ridge	+80