

Subdivisions of T. 3 North Range 35 East.

Chains.		
40.00	Set temp. $\frac{1}{4}$ Sec. cor.	Var. 20° East.
79.77	Intersect East bdy. 14 lks. S. of cor. to Secs. 11,12, 13 & 14.	
	Thence S. 89° 54' W. on true line.	
2.12	Wildhorse Creek Course N. W.	
	And set a stone 10x10x16 ins. 30 ins. in the ground for U.R. Meander Cor. Marked U.R. M.C. And raised a mound of stone alongside.	
5.27	Road Course N. E.	
15.15	Canon Course N.	-150
39.88	Set a post 3 ft. long 3 ins. sq. 24 ins. in the ground for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ S. on N. face. from which A pine 14 ins. diam. bears N. 15° E. 68 lks. dist. marked $\frac{1}{4}$ S B $\Psi$ . A pine 4 ins. diam. bears S. 35 lks. dist. marked $\frac{1}{4}$ S B $\Psi$ . and leave timber.	
45.00	Ascend. and leave pine thicket.	
59.60	Road course N. W.	
59.82	Set a post 3 ft. long 3 ins. sq. 24 ins. in the ground for 1/16 Sec. cor. Marked 1/16 on N. face. Dug pits 18x18x12 ins. E. & W. from post. 5 $\frac{1}{2}$ ft. dist. And raised a mound of earth 1 $\frac{1}{2}$ ft. high with 3 $\frac{1}{2}$ ft. base around post.	
69.50	Road Course N. W.	
79.77	To cor. to Secs. 10,11,14&15. Land hilly, some good bunch grass. Soil 1st rate. Heavy timber. .45.00 chs.	
	S. on true line bet. Secs. 14 & 15 Va. 20° East.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. N. & S. from stake 5 $\frac{1}{2}$ ft. dist. and raised a mound of earth 1 $\frac{1}{2}$ ft. high with 3 $\frac{1}{2}$ ft. base over it. And drove a stake, 2 ft. long & 2 ins. sq. in N. pit 12 ins. in the ground marked 1/16 on W. face.	