

Subdivisions of Township 3 North Range 35 East

Chains			
22.50	Draw Course S. W.		-20
40.00	Set a stone 12x8x6 ins. 6 ins. in the ground for $\frac{1}{4}$ Sec. cor, marked $\frac{1}{4}$ on W. face. Dug pits 18x18x12 ins. N. & S. from stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it		
42.50	Head of Canon Course W.		-30
60.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. dug pits 18x18x12 ins. N. & S. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. sq: 12 ins. in the ground, marked 1/16 S. on W. face.		
80.00	Set a stone 10x10x8 ins. 7 ins. in the ground for cor. to Secs. 14, 15, 22 & 23. Marked with 3 notches on S. and 2 on E. edges. Dug pits 18x18x12 ins. in each Sec. $5\frac{1}{2}$ ft. dist. And raised a mound of earth 2 ft. high with $4\frac{1}{2}$ ft. base alongside. Land rolling, Soil 1st rate. Good bunch grass.		
	East on randon bet. 14 & 23		
		Va. 20° East	
79.50	Set temp. cors. at 20, 40 & 60 chs. And at Intersect E. bdy. 70 lks. S. of cor. to Secs. 13, 14, 23 & 24. Thence S. 89° 30' W. on true line		
10.25	Road Course N. & S.		
19.89	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In E. pit set a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.		
39.75	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. cor. dug pits 18x18x12 ins. E. & W. from stake $5\frac{1}{2}$ ft. dist. raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over		