

Subdivisions of Township 3 North Range 35 East

Chains	
	it. In E. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.
56.00	Road course N. E.
59.62	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
79.50	To corner to Secs. 14, 15, 22 & 23. Land rolling, soil 1st rate, good grass.
South on true line bet. Secs. 22 & 23	
Va. 20° East.	
8.50	Road Course E. and W.
20.00	Set a stone 12x12 x6 8 ins. in the ground for 1/16 Sec. cor. marked with 1/16 on W. face. Dug pits 18x18x12 N. and S. from stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it.
40.00	Set a stone 12x10x10 ins. 8 ins. in the ground for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ on W. face. Dug pits 18x18x12 ins. N. & S. from stone $5\frac{1}{2}$ ft. dist. And raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over stone.
50.00	Canon Course S. W.
60.00	Set a stone 12x10x5 ins. 8 ins. in the ground for 1/16 Sec. Cor. marked 1/16 on W. face. Dug pits 18x18x12 ins. N. and S. from stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it.
80.00	Deposited marked stone and charred stake 12 ins. in the ground for Cor. to Secs. 22, 23, 26 & 27 and dug pits 18x18x12 ins. in each Sec. $5\frac{1}{2}$ ft. dist. And raised a mound of earth 2 ft. high with $4\frac{1}{2}$ ft. base over it. In S. E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground. marked T. 3 N. S., 23 on N. E. R. 35. E., S 26 on S. E. S. 27 on S. W. and S. 22 on N. W. faces with 2 notches on S. and E. edges.