

41

Subdivisions of Township 3 North Range 35 East

Chains	
	Land rolling, soil 1st rate, good grass.
	East on random bet. Secs. 23 & 26 Va. 20° East.
79.50	Set temp. cor. 20, 40, and 60 chs. and at Intersect E. bdy. 68 lks. S. of cor. to Secs. 23, 24, 25 & 26.
19.87	Thence S. 89° 31' W. on true line Set a stone 12x10x8 ins. 8 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. And raised a mound of stone 1½ ft. high with 3½ ft. base over it.
39.75	Deposited a charred stake 12 ins. in the ground for 1/16 Sec. cor. dug pits 18x18x12 ins. E and W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked ¼ S. on N. face.
58.00	Begin to descend.
59.62	Set a stone 12x8x7 ins. 8 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Over which I raised a mound of stone 1½ ft. high with 4½ ft. base. Pits impracticable.
79.50	To cor. to Secs. 22, 23, 26 & 27. Land rolling and somewhat rocky, soil 2nd rate. Some grass.
	South on true line bet. Secs. 26 & 27. Va. 20° East.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. N. and S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked ¼ S. on W. face.
27.20	Road Course N. E.
40.00	Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake 5½ ft.