

Subdivisions of Township 3 North Range 35 East

Chains		
	South on random bet. secs 34 & 35 Va. 21° 30' East	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.36	Intersect Township line 3.88 chs. W. of cor. to Secs. 34 & 35 Thence N. 2° 45' W. on true line Descend	
10.50	Wagon Road in river bottom	-80
15.00	O. R. and N. Railroad Course E. and W.	
36.00	Umatilla River 1.00 chs. wide runs W.	
39.40	Set a stone 12x10x8 ins. 8 ins. in the ground for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ on W. face and raised a mound of stone 1 $\frac{1}{2}$ ft. high with 3 $\frac{1}{2}$ ft. base over stone. Ascend Steep bluff.	
75.00	Summit of ridge on hill	1800
79.45	To cor. to Secs. 26, 27, 34 & 35 Land, rough and mountainous 75 chs. Balm and cottonwood timber along river bottom. Some grass Soil 1st rate Aug. 25, 1887.	
	From the corner to Secs. 3, 4, 33 & 34 on the N. bdy. of the Tp. I run south on line bet. Secs. 3 & 4 Va. 21° East.	
	Through field	
40.00	Begin to descend	
68.85	Intersect U.R. bdy. Set a stone 14x12x10 ins. 10 ins. in the ground for meander cor. To fractional Secs. 3 & 4 marked U.R.M.C. from which A balm 20 ins. diam. bears S. 12 lks. dist. marked T 3 N R. 35 E., M.C. B.T. No other tree within limits.	
72.00	Enter barn lot. House bears W. 2.50 chs.	
80.00	Deposited charred stake 12 ins. in the ground for cor. to Secs. 3, 4, 9 & 10. Dug pits 18x18x12 ins. in each Sec. 5 $\frac{1}{2}$ ft. dist. from stake, and raised a mound of	