

Subdivisions of Township 3 North Range 35 East

Chains	
	<p>earth 2 ft. high with $4\frac{1}{2}$ ft. base over it. In S. E. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked T 3 N S., 3 on N E., R 35 E., S 10 on SE. S 9 on SW. and S 4 on NW. faces with 5 notches on S. and 3 on E. edges.</p> <p>Land rolling, Soil 1st rate. Mostly cultivated N. of Wild Horse creek.</p>
	<p>East on random bet. Secs. 3 & 10 Va. 20° East.</p> <p>Set temp. cor.s at 20.40 and 60.00 chs. And at</p> <p>77.75 Intersect E. bdy. 50 lks. S. of cor. to Secs. 2, 3, 10 & 11. Thence S. 89° 38' W. On true line</p> <p>16.50 Road Course N. and S.</p> <p>19.38 Set a post 3 ft. long 3 ins. sq. 24 ins. in the ground for $\frac{1}{16}$ Sec. cor. marked $\frac{1}{16}$ S. on N. face Dug pits 18x18x12 ins. E. & W. from post $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base around post.</p> <p>38.77 Set a post 3 ft. 3 ins. sq. 24 ins. in the ground for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on N. face. Dug pits 18x18x12 ins. E. and W. from post. $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base around post</p> <p>44.25 Road Course N. & S.</p> <p>45.00 Enter pasture.</p> <p>58.15 Set a post 3 ft. long 3 ins. sq. 24 ins. in the ground for $\frac{1}{16}$ $\frac{1}{16}$ Sec. cor. marked $\frac{1}{16}$ on N. face. Dug pits 18x18x12 ins. E. & W. from post $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base around post.</p> <p>77.55 To Cor. to Secs. 3, 4, 9 & 10. Land, rolling, soil 1st rate, not cultivated.</p>