

Subdivisions of Township 3 North Range 35 East.

Chains		
	South on true line bet. Secs. 9 & 10 <div style="text-align: right;">Va. 20° East.</div>	
10.25	Spring branch Course N. W.	-20
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. and dug pits. 18x18x12 ins. N. and S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In North pit set a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on W. face.	
38.00	Fence Course E. and W.	
40.00	Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. dug pits 18x18x12 ins. N. & S. from stake 5½ ft. dist. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked ¼ S. on W. face.	
60.00	Deposited charred stake 12 ins. in the ground for 1/16 Secs. cors. Dug pits 18x18x12 ins. N. and S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on W. face.	
80.00	Set a stone 10x10x8 ins. 7 ins. in the ground for cor. to Secs. 9, 10, 15 & 16. Marked with 4 notches on S. and 3 on E. edges. Dug pits 18x18x12 ins. in each Sec. 5½ ft. dist. And raised a mound of earth 2 ft. high with 4½ ft. base alongside. Hand rolling. Soil 1st rate, partly under cultivation W. of line Good Grass.	
	East on random bet. Secs. 10 & 15 <div style="text-align: right;">Va. 22° East.</div>	
	Set temp. Cors. At 20.40 and 60.00 chs. and at	
77.50	Intersect E. bdy. 50 lks. S. of Cor. to Secs. 10, 11, 14 & 15.	