

Subdivisions of Township 3 North Range 35 East

Chains	
	Thence S 89° 38' W. on true line.
19.38	Set a post 3 ft. long 3 ins. square 24 ins. in the ground for 1/16 Sec. cor. marked 1/16 S. on N. face. Dug pits 18x18x12 ins. E. and W. from post 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base around post.
38.75	Set a post 3 ft. long 3 ins. square 24 ins. in the ground for ¼ Sec. cor. marked ¼ S. on N. face. Dug pits 18x18x12 ins. E. & W. from post 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base around post.
47.00	Wagon Road Course N.
58.13	Set a post 3 ft. long 3 ins. square 24 ins. in the ground for 1/16 Sec. Cor. marked 1/16 S. on N. face. Dug pits 18x18x12 ins. E. & W. from post 5½ ft. dist. and raise a mound of earth 1½ ft. high with 3½ ft. base around post.
69.00	Road Course N. & S.
75.00	Road Course N. & S.
77.50	To Cor. to Secs 9, 10, 15 and 16. Land rolling, uncultivated. Soil 1st rate, good grass.
South on true line bet. Secs. 15 and 16. Va. 22° East.	
6.00	Gulch Course N. W.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. and S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on W. face. And ascend side of hill.
40.00	Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x12 ins. N. and S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base. over it. In N. pit drove a stake 2 ft. long