

Subdivisions of Township 3 North Range 35 East

| Chains | |
|--------|---|
| 60.00 | <p>2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S. on W. face.</p> <p>Deposited a charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on W. face</p> |
| 76.50 | Wagon Road Course N. E. |
| 80.00 | <p>Deposited charred stake 12 ins. in the ground for cor. to Secs. 15, 16, 21 & 22. Dug pits 18x18x12 ins. in each Sec. $5\frac{1}{2}$ ft. dist. And raised a mound of earth 2 ft. high with $4\frac{1}{2}$ ft. base over it. In S. E. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked T. 3 N S., 15 on N. E. R 35 E., S. 22 on S. E. S 21 on S. W. and S 16 on N. W. faces with 3 notches on S. and E. edges</p> <p>Land rolling, Uncultivated.</p> <p>Good Bunch Grass.</p> <p>Soil 1st rate.</p> |
| 77.45 | <p>East on random bet. Secs. 15 & 22.</p> <p style="text-align: right;">Va. 21° East.</p> <p>Set temp. Cor at 20, 40, and 60, chs. and at Intersect E. bdy. 38 lks. S. of cor. to Secs. 14, 15, 22 and 23. Thence</p> <p>S. $89^{\circ} 43'$ W. on true line.</p> |
| 19.36 | <p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p> |
| 23.00 | Road Course S. W. |
| 38.72 | <p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake $5\frac{1}{2}$ ft.</p> |