

Subdivisions of Township 3 North Range 35 East

Chains		-100
32.75 38.70	<p>In E. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face</p> <p>Canon below spring branch course S.</p> <p>Set a stone 18x15x12 ins. 12 in the ground for 1/4 Sec.</p> <p>Cor. marked 1/4 on N. face Dug pits 18x18x12 ins. E. & W. from stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high with 3 1/2 ft. base over it.</p>	
58.05	<p>Set a stone 12x6x6 ins. 8 ins. in the ground for 1/16 Sec. Cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E. & W. from stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high with 3 1/2 ft. base over it.</p>	
77.40	<p>To Cor. to Secs. 27, 28, 33 and 34.</p> <p>Land rolling, not cultivated.</p> <p>Good grass.</p> <p>Soil 1st rate.</p>	
<p>South on random bet. Secs. 33 & 34.</p> <p style="text-align: center;">Va. 22° East.</p>		
79.45	<p>Set temp. Cors. at 20, 40, 60 chs. And at</p> <p>Intersect Township line 1.20 chs. W. of Cor. to Secs. 33 & 34. Thence</p> <p>N. 0° 52' W. on true line</p>	
39.45	<p>Set a stone 20x12x14 ins. 14 ins. in the ground for 1/4 Sec. cor. marked 1/4 on W. face. Dug pits 18x18x12 ins. N. & S. from stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high with 3 1/2 ft. base over it.</p>	
59.45	<p>Set a stone 14x8x6 ins. 9 ins. in the ground for 1/16 Sec. Cor. marked 1/16 on W. face. Dug pits 18x18x12 ins. N. & S. from stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high with 3 1/2 ft. base over it.</p>	
79.45	<p>To Cor. to Secs. 27, 28, 33 & 34.</p> <p>Land rolling, uncultivated, good grass.</p> <p>Soil 1st rate.</p>	
<p>From corner to Secs. 4, 5, 32 & 33 on the North bdy. of Township I run</p>		