

Subdivisions of Township 3 North Range 35 East.

Chains	South on true line bet. Secs. 4 & 5. Va. 20° East.
10.00	Enter field and gradually ascend.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on W. face.
40.00	Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked ¼ S. on W. face
60.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on W. face.
80.00	Deposited charred stake 12 ins. in the ground for Cor. to Secs. 4, 5, 8 & 9. Dug pits 18x18x12 ins. in each Sec. 5½ ft. dist. and raised a mound of earth 2 ft. high with 4½ ft. base over it. In S. E. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked T 3 N S 4, on N. E., R 35 E., S 9 On S. E., S 8 on S W. and S 5 on N. W. faces with 4 notches on E. and 5 on S. edges. Land slightly rolling or sloping toward the North. All under cultivation. Soil 1st rate.
79.60	East on random bet. Secs. 4 and 9. Va. 20° East. Set temp. Cors. At 20, 40, and 60 chs. And at Intersect E. bdy. 50 lks. S. of Cor. to Secs. 3, 4, 9 & 10.