

Subdivisions of Township 3 North Range 35 East

Chains		
	Thence S 89° 39' W. on true line	
1.75	Enter field of Mr. Simpson	
19.90	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In East pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N face.	
35.25	Gulch Course N. W.	-100
39.80	Deposited a charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In East pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked ¼ S. on N. face.	
41.50	Partition fence and enter another field.	
59.70	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In East pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.	
79.60	To Cor. to Secs. 4, 5, 8 & 9. Land rolling, all under cultivation. Soil 1st rate.	
	South on true line bet. Secs. 8 & 9. Va. 20° East. Ascend gradual sloping hill.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on W. face.	
23.40	Lane and Road Course N. W. Enter field	+250