

Subdivisions of Township 3 North Range 35 East.

Chains	
60.00	<p>dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In East pit drove a stake 2 ft. long 2 ft. sq. 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In East pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.</p>
80.00	<p>To Cor. to Secs. 8, 9, 16 & 17.</p> <p>Land rolling, Soil 1st rate, mostly uncultivated.</p>
<p>South on true line bet. Secs. 16 & 17.</p> <p>Va. 21° East.</p>	
7.05	<p>Leave field of Hank Vaughn</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. dug pits 18x18x12 ins. N. & S. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. and $3\frac{1}{2}$ ft. base over it. In North pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on W. face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. Cor. dug pits 18x18x12 ins. N. & S. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In N. pit drove a stake 2 ft. long and 2 ins. sq. 12 ins. in the ground marked $\frac{1}{4}$ S. on West face.</p>
57.75	<p>Fence and enter field.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. and S. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In North pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on W. face.</p>
80.00	<p>Deposited charred stake 12 ins. in the ground for to Secs. 16, 17, 20 & 21. Dug pits 18x18x12 ins. in</p>