

Subdivisions of Township 3 North Range 35 East

Chains	<p>each Sec. $5\frac{1}{2}$ ft. dist. and raised a mound of earth 2 ft. high with $4\frac{1}{2}$ ft. base over it. in S. E. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked T 3 N. S. 16 on N. E., R 35 E. S 21 on S. E., S. 20 on S. W. and S 17 on N. W. faces with 3 notches on S. & 4 on E. edges.</p> <p>Land rolling and mostly cultivated.</p> <p>Soil 1st rate.</p>
80.24	<p>East on random bet. Secs. 16 & 21.</p> <p style="text-align: center;">Va. $19^{\circ} 45'$ East.</p> <p>Set Temp Cors. At 20, 40, and 60 chs. And at Intersect East bdy. 15 lks. N. of cor. to Secs. 15, 16, 21 & 22.</p> <p>Thence N. $89^{\circ} 54'$ W. on true line.</p>
1.45	Wagon Road Course N.
7.75	Wagon Road Course N. W.
20.06	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ Sec. Cor. Dug pits $18 \times 18 \times 12$ ins. E. & W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In East pit drove a stake 2 ft. long & 2 ins. sq. 12 ins. in the ground marked $\frac{1}{16}$ S. on N. face.</p>
40.12	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec Cor. Dug pits $18 \times 18 \times 12$ ins. E. & W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long and 2 ins. sq. 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.</p>
60.18	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ Sec. Cor. Dug pits $18 \times 18 \times 12$ ins. E. & W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In East pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked $\frac{1}{16}$ S. on N. face.</p>
64.55	Fence and enter field course N. & S.