

Subdivisions of Township 3 North Range 35 East.

Chains 80.24	To cor. to Secs. 16, 17, 20 & 21. Land partly under cultivation, and gently rolling. Soil 1st rate.	
	South on true line bet. 20 & 21. Va. 19° 45' East.	
16.10	Fence and leave field course N. E.	
20.00	Deposited a charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long & 2 ins. sq. 12 ins. in the ground marked 1/16 S. on W. face.	
40.00	Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In North pit drove a stake 2 ft. long & 2 ins. sq. 12 ins. in the ground marked ¼ S. on W. face	
43.00	Spring Branch Course N. E.	-50
52.00	Dwelling house bears E. 2.00 chs. dist.	
55.00	Leave garden.	
60.00	Set a stone 7x8x9 ins. 6 ins. in the ground for 1/16 Sec. cor. marked 1/16 on W. face. Dug pits 18x18x12 ins. N. & S. from stone 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. And begin to descend.	
80.00	Set a post 4 ft. long 4 ins. sq. 24 ins. in the ground for Cor. to Secs. 20, 21, 28 & 29. Dug pits 18x18x12 ins. in each Sec. 5½ ft. dist. raised mound of earth 2 ft. high 4½ ft. base around post. Which I mark T 3 N 21 on NE., R 35 E., S 28 on S E., S 29 on S W., and S 20 on N W. faces with 4 notches on E. and 2 on S. edges. Land rolling, partly cultivated. All good agricultural land. Soil 1st rate.	