

Subdivisions of Township 3 North Range 35 East.

Chains.	East on random line bet. Secs. 21 & 28. Va. 20° 15' East. Set temp Cor. at 20, 40, and 60 chs. And at	
80.00	Intersect N. & S. line 50 lks. south of Cor. to Secs. 21 22, 27 & 28. Thence S 89° 39' W. on true line.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In East pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on North face.	
40.00	Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. dug pits 18x18x12 E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In. East pit drove a stake 2 ft. long & 2 ins. sq. 12 ins. in the ground marked ¼ S. on N. face.	
50.00	Dry ditch Course N. W.	-20
60.00	Deposited a charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In East pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.	
80.00	To Cor. to Secs. 20, 21, 28 & 29. Land rolling. Not cultivated. Spil 1st rate. Good grass.	
	South on true line bet. Secs 28 & 29 Va. 20° 15' East.	
20.00	Set a post 3 ft. long 3 ins. sq. 24 ins. in the ground for 1/16 Sec. Cor. marked 1/16 S. on W. face. dug pits 18x18x12 ins. N. & S. from post 5½ ft. dist. And raised a mound of earth 2 ft, high with 3½ ft. base around post	