

Subdivisions of Township 3 North Range 35 East.

Chains  
40.00 Deposited charred stake 12 ins. in the ground for  $\frac{1}{4}$  Sec. Cor. Dug pits 18x18x12 ins. N & S. from stake  $5\frac{1}{2}$  ft. dist. and raised a mound of earth  $1\frac{1}{2}$  ft. high with  $3\frac{1}{2}$  ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked  $\frac{1}{4}$  S. on W. face.

60.00 Set a stone 9x8x7 ins. 6 ins. in the ground for 1/16 Sec. Cor. marked 1/16 on W. face. Dug pits 18x18x12 ins. N. & S. from stone  $5\frac{1}{2}$  ft. dist. and raised a mound of earth  $1\frac{1}{2}$  ft. high with  $3\frac{1}{2}$  ft. base over it.

80.00 Set a stone 8x9x7 ins 6 ins. in the ground for Cor. to Secs. 28, 29, 32 & 33. Marked with 4 notches on E. and 1 on S. edges. Dug pits 18x18x12 ins. in each Sec.  $5\frac{1}{2}$  ft. dist. from stone and raised a mound of earth 2 ft. high with  $4\frac{1}{2}$  ft. base over stone.

Land level.  
Soil 1st rate.  
Good grass. Aug. 26, 1887.

East on random bet. Secs, 28 & 33.

Va. 21° East.

Set temp. Cors at 20, 40 and 60 chs. And at

80.12 Intersect N. & S line 47 lks. S. of Cor. to Secs. 27, 28, 33 and 34.

Thence S. 89° 40' W. on true line.

20.03 Set a post 3 ft. long & 3 ins. square 24 ins. in the ground for 1/16 Sec. Cor. marked 1/16 S. on N. face. Dug pits 18x18x12 ins. E. & W. from post  $5\frac{1}{2}$  ft. dist. and raised a mound of earth  $1\frac{1}{2}$  ft. high with  $3\frac{1}{2}$  ft. base around post.

40.06 Set a post 3 ft. long & 3 ins. square 24 ins. in the ground for  $\frac{1}{4}$  Sec. Cor. marked  $\frac{1}{4}$  S. on N. face. Dug pits 18x18x12 ins. E. & W. from post  $5\frac{1}{2}$  ft. dist. and raised a mound of earth  $1\frac{1}{2}$  ft. high with  $3\frac{1}{2}$  ft. base around post.

48.50 Canon Course South