

Subdivisions of Township 3 North Range 35 East

Chains 52.25	Wagon Road Course South. Ascend.	
60.09	Set a stone 7x8x9 ins. 6 ins. in the ground for 1/16 Sec Cor. marked 1/16 on N. face and raised a mound of stone 1 1/2 ft. high with 3 1/2 ft. base over it. Pits impracticable.	
80.12	To Cor. to Secs. 28, 29, 32 & 33. Land rolling, not under cultivation. Good grass, Soil 1st rate.	
South on random bet. 32 & 33.		
Va. 21° East.		
79.78	Set temp. Cor at 20, 40 and 60 chs. And at Intersect Township line 198 lks. W. of Cor. to Secs 32 & 33. Thence N. 19 25' W. on true line.	
16.65	Canon Course S. W.	-75
17.75	Old Stage Road Course S. W.	
30.50	Canon Course East	-50
39.78	Set a stone 12x8x7 ins. 8 ins. in the ground for 1/4 Sec. Cor. marked 1/4 on W. face. Dug pits 18x18x12 ins. N. & S. from stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high with 3 1/2 ft. base over it	
59.78	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. & S. of stake 5 1/2 ft. dist. and raised mound of earth 1 1/2 ft. high 3 1/2 ft. base over it. In N. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on W. face.	
62.80	Canon Course E.	-50
79.78	To Cor to Secs. 28, 29, 32 & 33 Land steep & mountainous, some rock. 79.78 chs. Good grass. Soil 1st rate.	-400