

Subdivisions of Township 3 North Range 35 East.

Chains 16.00	Fence and leave field N. E. and S. W.
17.38	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.
37.38	Deposited charred stake 12 ins. in the ground for ¼ Sec. dug pits 18x18x12 ins. E. and W. from stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. In E. pit drove a stake 2 ft. long & 2 ins. square, 12 ins. in the ground marked ¼ S. on N. face.
57.38	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In E. pit drove a stake 2 ft. long & 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.
59.25	Fence and field of Hank Vaughn Course North W. and S. E.
77.38	To cor. to Secs. 5, 6, 7 & 8 Land rolling. Partly cultivated.. Soil 1st rate.
South on true line bet. Secs. 7 & 8. Va. 20° East.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. N. and S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long & 2 ins. square, 12 ins. in the ground marked 1/16 S. on W. face.
36.50	Leave field of H. Vaughn
40.00	Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it.