

## Subdivisions of Township 3 North Range 35 East.

Chains	
60.00	<p>In N. pit drove a stake 2 ft. long &amp; 2 ins, square, 12 ins. in the ground marked <math>\frac{1}{2}</math> S. on W. face.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. &amp; S. from stake <math>5\frac{1}{2}</math> ft. dist. and raised a mound of earth <math>1\frac{1}{2}</math> ft, high with <math>3\frac{1}{2}</math> ft. base over it. In N. pit drove a stake 2 ft. long. &amp; 2 ins. square, 12 ins. in the ground marked 1/16 S. on W. face.</p>
80.00	<p>Deposited charred stake 12 ins. in the ground for Cor. to Secs. 7, 8, 17 &amp; 18. Dug pits 18x18x12 ins. in each Sec. <math>5\frac{1}{2}</math> ft. dist. and raised a mound of earth 2 ft. high with <math>4\frac{1}{2}</math> ft. base over it. In S. E. pit drove a stake 2 ft. long &amp; 2 ins. square, 12 ins. in the ground marked T 3 N S 8 on N.E., R 35 E S 17 on S. E., S 18 on S. W. and S 7 on N.W. faces, with 5 notches on E. and 4 notches on S. edges.</p> <p>Land slightly rolling. Mostly under cultivation. Good Agricultural land. Soil 1st rate.</p>
80.04	<p>East on random bet. Secs. 8 &amp; 17.</p> <p style="text-align: right;">Va. 20° 15' East.</p> <p>Set temp. Cors at 20, 40, 60 chs. And at</p> <p>Intersect N. &amp; S line at cor. to Secs. 8, 9, 16 &amp; 17.</p> <p>Thence West</p> <p>On true line.</p>
20.01	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec/ Cor. Dug pits 18x18x12 ins. E. &amp; W. from stake <math>5\frac{1}{2}</math> ft. dist. and raised a mound of earth <math>1\frac{1}{2}</math> ft. high with <math>3\frac{1}{2}</math> ft. base over it. In E. pit drove a stake 2 ft. long &amp; 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> Sec. Cor. Dug pits 18x18x12 ins. E. &amp; W. from stake <math>5\frac{1}{2}</math> ft. dist. and raised a mound of earth <math>1\frac{1}{2}</math> ft. high with <math>3\frac{1}{2}</math> ft. base over it.</p>