

Subdivisions of Township 3 North Range 35 East

Chains	
77.43	<p>base over it. In E. pit drove a stake 2 ft. long &amp; 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p> <p>To Cor. to Secs. 7, 8, 17 &amp; 18.</p> <p>Land level.</p> <p>Soil 1st rate Good grass.</p>
20.00	<p>South on true line bet. Secs. 17 &amp; 18.</p> <p style="text-align: right;">Va. 20° 15' East.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16' Sec. Cor. Dug pits 18x18x12 ins. N. and S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long &amp; 2 ins. square, 12 ins. in the ground marked 1/16 S. on W. face.</p>
28.50	Wagon Road in lane course N. W.
34.00	Spring branch course N. W.
40.00	<p>Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x12 ins. N. and S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long &amp; 2 ins. square, 12 ins. in the ground marked ¼ S. on W. face.</p>
54.60	Fence and leave field course N. E.
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. &amp; S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In E. pit drove a stake 2 ft. long &amp; 2 ins. square, 12 ins. in the ground marked 1/16 S. on W. face.</p>
80.00	<p>Deposited charred stake 12 ins. in the ground for Cor. to Secs. 17, 18, 19 &amp; 20. Dug pits 18x18x12 ins. in each Sec. 5½ ft. dist. and raised a mound of earth 2 ft. high with 4½ ft. base over it. In S. E. pit drove a stake 2 long &amp; 2 ins. square 12 ins. in the ground marked T 3 N S. 17 N. E., R 35 E., S 20 on S. E., S 19 on S W. and S 18 on N. W. faces, with 5 notches on E. and 3 on S.</p>