

Subdivision of Township 3 North Range 35 East.

Chains.	<p>dist. and raised a mound of earth <math>1\frac{1}{2}</math> ft. high with <math>3\frac{1}{2}</math> ft. over it. In N. pit drove a stake 2 ft. long 2 ins. square, 12 ins. in the ground marked <math>\frac{1}{4}</math> S. on W. face.</p> <p>60.00 Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. &amp; S. from stake <math>5\frac{1}{2}</math> ft. dist, and raised a mound of earth <math>1\frac{1}{2}</math> ft. high with <math>3\frac{1}{2}</math> ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. square, 12 ins. in the ground marked 1/16 S. on W. face.</p>
80.00	<p>Deposited charred stake 12 ins. in the ground for Cor. to Secs. 19, 20, 29 &amp; 30. Dug pits 18x18x12 ins. in each Sec. <math>5\frac{1}{2}</math> ft. dist. and raised a mound of earth 2 ft. high with <math>4\frac{1}{2}</math> ft. base over it. In S. E. pit drove a stake 2 ft. long 2 ins. square, 12 ins. in the ground marked T 3 N S. 20 on N. E., R 35 E S. 29 on S. E., S 30 on S W. and S 19 on N. W. faces with 5 notches on E. and 2 on S edges.</p> <p>Land level and mostly cultivated.</p> <p>Soil 1st rate.</p>
<p>East on random bet. Secs 20 &amp; 29</p>	
<p style="text-align: right;">Va. <math>21^{\circ}</math> East.</p>	
80.00	<p>Set temp. Cors. at 20, 40 and 60 chs. and at Intersect N. &amp; S. line 15 lks. S. of the cor. to Secs. 20, 21, 28 &amp; 29. Thence S. <math>89^{\circ} 54'</math> W.</p> <p>On true line.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. &amp; W. from stake <math>5\frac{1}{2}</math> ft. dist. and raised a mound of earth <math>1\frac{1}{2}</math> ft. high with <math>3\frac{1}{2}</math> ft. base over it. In E pit drove a stake 2 ft. long 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> Sec. Cor. Dug pits 18x18x12 ins. E. &amp; W. from stake <math>5\frac{1}{2}</math> ft. dist. and raised a mound of earth <math>1\frac{1}{2}</math> ft. high with <math>3\frac{1}{2}</math> ft. base over it. In E. pit drove a stake 2 ft. long</p>