

Subdivisions of Township 3 North Range 35 East.

Chains	2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.
55.00	Fence and leave field.
60.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. over it. In East pit drove stake 2 ft. long 2 ins. square, 12 ins. in the ground marked $\frac{1}{16}$ S. on N. face.
80.00	To Cors. to Secs. 19, 20, 29 & 30.
Land	Land rolling. Partly under cultivation. Soil 1st rate.
	West on Random Bet. Secs. 19 and 30. Va. 21° East.
77.24	Set temp. Cors. at 20, 40 and 60 chs. and at Intersect Township line 12 lks. N. of Cors. to Secs. 24, 25, 19 and 30. Thence N. $89^{\circ} 55'$ E. on true line.
17.24	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ Sec. Cor. Dug pits 18x18x12 ins. ins. E. and W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. square, 12 ins. in the ground marked $\frac{1}{16}$ S. on N. face.
37.24	Deposited charred stake 12 ins. in the ground, for $\frac{1}{4}$ Sec. Cor. Dug pits 18x18x12 ins. E. and W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. square, and 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.
42.00	Dwelling house bears N. 350 lks. dist.
57.24	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ Sec. Cor. Dug pits 18x18x12 ins. ins, E. and W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. with $3\frac{1}{2}$ ft. base over it.