

Allotment

Section 11

Subdivision of Township 3 North Range 35 East.

Chains.	
	<p>From the corner to Secs. 10 & 11, 14 & 15 which is a post 4 ins. square firmly set in ground marked T 3 N S. 11 on N E., R 35 E., S 14 on S E., S 15 on S. W., and S 10 on N. W. faces, pits 18x18x12 ins. in each Sec. 5½ ft. dist & mound of earth 2 ft. high 4½ ft. base around post. I run</p>
	<p>N 89° 54' E. on true line. bet Secs. 11 & 14</p>
	<p>Var. 19° E.</p>
19.94	<p>Set a post 3 ft. long 3 ins. sq. 24 ins. in the ground for 1/16 Sec. cor. marked 1/16 S. on N. face. Dug pits 18x18x12 ins. E. & W. of post 5½ ft. dist. and raised mound of earth 1½ ft. high with 3½ ft. base over it.</p>
26.90	<p>Descend.</p>
29.91	<p>Set basalt stone 11x8x6 ins. 7 ins. in the ground for 1/32 Sec. corner marked 1/32 on N. face, dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. and raised mound of earth 1½ ft. high 3½ ft. base over it.</p>
	<p>Corner on N. slope.</p>
39.88	<p>Intersect the ¼ Sec. corner bet Secs. 11 & 14 which is a post 3 ins. sq. marked ¼ S. on N. face., firmly set in the ground from which</p> <p>A pine 14 ins. diam. brs. N.15° E. 68 lks. dist. marked ¼ S B T.</p> <p>A pine 4 ins. diam. brs. S. 35 lks. dist. marked ¼ S B T.</p>
	<p>Land rolling.</p>
	<p>Soil 1st rate.</p>
	<p>Good Grass.</p>
	<hr/> <p>From the 1/16 Sec. corner 20 chs. N. of the corner to Secs. 10 & 11, 14 and 15 which is a post 3 ins. sq. firmly set in the ground marked 1/16 S. on W. face. Pits 18x18x12 ins. N. & S. of post 5½ ft. dist. & mound of earth 1½ ft. high 3½ ft. base around post.</p> <p>I run</p> <p>East on true line in Sec. 11.</p> <p>Var. 20° East</p>