

## Allotment

## Section 13

## Subdivision of Township 3 North Range 35 East.

Chains	Pits impracticable.	-75
53.70	Gulch course S.	
62.77	Set stone 18x12x10 ins. 14 ins. in the ground for 1/16 Sec. corner marked 1/16 on N. face and raised a mound of stone over it	C
83.70	<p>Pits impracticable.</p> <p>To the 1/16 Sec. corner 20 chains N. of the corner to Secs. 13, 14, 23 and 24.</p> <p>Land along W. rocky.</p> <p>Slope soil 2nd rate.</p> <p>Some grass.</p> <p style="text-align: right;">June 8, 1889</p>	
10.00	<p>From the <math>\frac{1}{4}</math> Sec. corner between Secs. 13 &amp; 14.</p> <p>I run</p> <p>North between Secs. 13 &amp; 14 on true line</p> <p style="text-align: right;">Var. 21° E.</p> <p>Descending.</p> <p>Set stone 10x7x6 ins. 8 ins. in the ground for 1/32 Sec. corner marked 1/32 on S. face, from which</p> <p>A pine 16 ins. diam. bears S 35° W. 18 lks.</p> <p>dist marked 1/32 S B T. and raised a mound of stone over it.</p> <p>Land sloping to N.W.</p> <p>Soil 1st rate.</p> <p>Good grass.</p>	E