

81
Allotment
Section 13

Subdivisions of Township 3 North Range 35 East.

Chains. From 1/32 Sec. corner 10 chs. N. of $\frac{1}{2}$ Sec. corner bet. Secs.
13 & 14. I run
East on true line in Sec 13.
Var. 19° East.
Along E. slope.
20.80 Set stone 10x8x8 ins. 7 ins. in the ground for 1/32 Sec.
Corner marked 1/32 on W. face, dug pits 18x18x12 ins.
N. & S. of stone $5\frac{1}{2}$ ft. dist. raised a mound of earth
 $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.
Land rolling & soil 1st rate.
Grass and some pine brush.

Section -24-

From the corner to Secs. 13-18-19 and 24 which is a post
4 ins. square firmly set in the ground marked T 3 N.,
S 13 on N.W., R 36 E., S 18 on N.E., S 19 on S E., &
R 35 E., S 24 on S W., with 3 notches on N. & S. edges
from which
A pine 18 ins. diam. bears N. 8° E. 59 lks. dist.
marked T 3 N R 36 E., S 18 B T.
A pine 36 ins. diam. bears S 65° W. 122 lks. dist.
marked R 35 E., S 24 B T. & dug pits 18x18x12 ins.
in Secs. 13 & 18 & mound of earth alongside.
I run
West on random line between Secs. 13 and 24
Var. 18° 45' E.
Setting temporary corner at 19.80 chains and at
41.62 Intersect the $\frac{1}{4}$ Sec. corner between Secs 13 & 24, which
is a stone 12x8x7 ins. 8 ins. in the ground marked $\frac{1}{4}$
on N. face, with pits 18x18x12 ins. E & W. of stone $5\frac{1}{2}$
ft. dist. & mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over
it. Thence I run
East on true line between secs. 13 & 24.
Var. 19° E.
Through timber.