

Allotment

Section 24

Subdivisions of Township 3 North Range 35 East

Chains	
2.00	ft. base alongside. I run West on true line between Secs. 24 and 25. Var 22° East. Gulch Course S.
20.90	Set stone 9x8x7 ins. 6 ins. in the ground for 1/16 & 1/32 on Sec. corner, marked 1/16 on N. & 1/32 on S. face, dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. & raised a mound of earth 1½ ft. high 3½ ft. base over it.
41.80	Intersect the ¼ Sec. corner which is a basalt stone 12x10 x8 ins. 8 ins. in the ground marked ¼ on N. face and mound of stone over it. Land rolling Soil 1st rate. Good grass.
50.00	From the 1/16 Sec. corner 20 chains West of the corner to Secs 19-24-25 & 30. I run North on random line in Sec. 24 Var. 20° E. Setting temporary corner at 20, 30 & 40 chains and at Intersect the East and W line at 1/32 Sec. corner 20 chs. W. & 10 chains N. of ¼ Sec. corner between Secs. 19 & 24. Thence I run South on true line in Sec. 24. Descend steep hill side
7.75	Gulch course W.
10.00	Set stone 9x8x7 ins. 6 ins. in the ground for 1/32 Sec. corner, marked 1/32 on W. face, from which A pine 20 ins. diam. brs N. 2° W. 112 lks. dist. marked 1/32 S B T. A pine 6 ins. diam. bears N. 1° E. 131 lks. dist. marked 1/32 S B T.
15.00	Summit course E. & W.
20.00	Set stone 9x8x7 ins. 6 ins. in the ground for 1/32 Sec. cor. marked 1/32 on W. face, and raised a mound of stone over it.