

Allotment

Section 25

Subdivision of Township 3 North Range 35 East

Chains	
	<p>E. & W. of stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.</p> <p>Land rolling.</p> <p>Soil 1st rate.</p> <p>Grass & sunflower.</p>
	<p>From the $\frac{1}{32}$ Sec. corner 10 chs. S. of $\frac{1}{4}$ Sec. corner between Sec. 24 & 25. I run North on random line in Section 25.</p> <p style="text-align: right;">Var. 21° E.</p>
10.00	<p>Intersect the E. & W. line at $\frac{1}{4}$ Sec. corner between Secs. 24 & 25.</p> <p>Thence I run South on true line in Sec. 25</p>
10.00	<p>To the $\frac{1}{32}$ Sec. corner.</p> <p>Land rolling.</p> <p>Soil 1st rate.</p> <p>Grass & Sunflower.</p>
	<p style="text-align: center;">Section 26</p> <p>From the $\frac{1}{4}$ Sec. corner between Secs. 23 & 26 which is a charred stake 12 ins. in the ground pits $18 \times 18 \times 12$ ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. & mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. In E pit a stake 2 ins. sq. marked $\frac{1}{4}$ S. in N. face. I run South on true line in Sec. 26.</p> <p style="text-align: right;">Var. $21^{\circ} 30'$ E.</p> <p>10.08 Trail course N. E & S. W.</p> <p>20.00 Set a basalt stone $12 \times 8 \times 6$ ins. 8 ins. in the ground on E. slope for $\frac{1}{16}$ Sec. corner. marked $\frac{1}{16}$ on W. face. dug pits $18 \times 18 \times 12$ ins. N. & S. of stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.</p> <p>A long branch of Canyon on E. to</p> <p>40.00 Set basalt stone $10 \times 10 \times 5$ ins. 7 ins. in the ground for $\frac{1}{4}$ Sec. corner marked $\frac{1}{4}$ on W. face, and raised a mound</p>