

49
Allotment

Section 26

Subdivision of Township 3 North Range 35 East.

| Chains | |
|--------|--|
| | <p>From the 1/16 Sec. 20 chs. N. of course to Secs. 26, 27, 34 & 35 which is a basalt stone 12x8x8 ins. 8 ins. in the ground marked 1/16 on W. face; with pits 18x18x12 ins. N. & S. of stone 5½ ft. dist. and mound of earth 1½ ft. high 3½ ft. base over it. I run East on random line in Sec. 26.</p> <p style="text-align: right;">Var. 20° E.</p> |
| 30.00 | <p>Setting temporary corner at 20.00 chains and at Intersect the N. & S. line 10 chs. N. of 1/32 Sec. corner. Thence I run N. 89° 49' W. on true line in Sec. 26</p> <p style="text-align: right;">Var. 20° E.</p> |
| 6.00 | <p>Trail course S.E.</p> |
| 10.00 | <p>Set basalt stone 12x8x5 ins. 8 ins. in the ground for 1/16 & 1/32 Sec. corner, marked 1/16 on N. & 1/32 on S. faces Dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. raised a mound of earth 1½ ft. high 3½ ft. base over it.</p> |
| 30.00 | <p>To the 1/16 Sec. corner 20 chs. N. of corner to Secs. 26, 27, 34 & 35.</p> <p>Land rolling. Soil 1st rate. Grass & sunflower.</p> |
| 10.00 | <p>From 1/16 Sec. corner 20 chs. N. of the corner to Secs. 26, 27, 34 & 35. I run South on true line between Secs. 26 & 27.</p> <p style="text-align: right;">Var. 20° East.</p> |
| 10.00 | <p>Set basalt stone 10x9x7 ins. 6 ins. in the ground for 1/32 Sec. corner, marked 1/32 on E. face dug pits 18x18x12 ins. N. & S. of stone 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it.</p> <p>Land rolling. Soil 1st rate. Good grass.</p> |
| | <p>From 1/32 Sec. corner 10 chs. N. of the corner to Secs. 26,</p> |