

Allotment

Section 31

Subdivision of Township 3 North Range 35 East.

Chains	<p>Pits impracticable. over it.</p> <p>Land mostly level.</p> <p>Soil 1st rate.</p> <p>Grass & sunflower.</p>	
	<p>From the 1/16 Sec. corner 20 chs. N. of corner to Tp. 3 N. Rs. 34 & 35 E. which is a post 3 ins. sq. firmly set in the ground marked 1/16 S. on W. face with pits 18x18x12 ins. on N. & S. of corner 5½ ft. dist. & mound of earth 1½ ft. high 3½ ft. base around post. I run</p> <p>N. 89° 55' E. on random line through the S ½ of Sec. 31 Var. 16½° E.</p> <p>Setting temporary corner at 17.70, 37.70 & 57.70 chs.</p> <p>And at</p>	
77.90	<p>Intersected the N. & S. line 12 lks. N. of 1/16 Sec. cor. bet. Secs. 31 & 32.</p> <p>Thence I run</p> <p>West on true line through the S. ½ of Sec. 31. Var. 17° E.</p>	
15.00	Gulch course S.	-100
20.00	<p>Set stone 12x10x5 ins. 8 ins. in the ground for 1/16 Sec. corner marked 1/16 on N. face. dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it.</p>	
40.00	<p>Set stone 14x9x8 ins. 10 ins. in the ground for 1/16 Sec. corner, marked 1/16 on N. face and raised mound of stone over it.</p> <p>Pits impracticable.</p>	
43.00	Gulch course S.	-200
55.00	Summit course S.	+200
60.00	<p>Set stone 12x10x7 ins. 9 ins. in the ground for 1/16 Sec. corner, marked 1/16 on N. face dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. and raised mound of earth 1½ ft. high 3½ ft. base over it.</p>	
77.90	<p>The 1/16 Sec. corner between Secs. 31 & 32.</p> <p>Land along line rocky & steep. Some grass.</p>	