

Allotment

Section 36

Subdivision of Township 3 North Range 35 East

| Chains | | +100 |
|--------|---|------|
| | Through brush. | |
| 11.25 | Brink of bluff. | |
| 13.00 | Squaw creek 10 lks. wide Course N. | |
| 18.00 | Foot of hill. | |
| 20.40 | Set stone 10x8x7 ins. 7 ins. in the ground for 1/32 Sec. corner, marked 1/32 on N. face, dug pits 18x18x12 ins. E. & W. of stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high 3 1/2 ft. base over it. | |
| 22.00 | Bench land. | |
| 35.00 | Fence course N. E. & enter brush. | |
| 46.80 | Set pine post 3 ft. long 3 ins. sq. 24 ins. in the ground for 1/32 & 1/4 Sec. corner in dense thickets, marked 1/4 on S. and 1/32 on N face, from which A cherry 3 ins. diam bears S. 70° E. 12 lks. dist. marked 1/4 & 1/32 S.B. T. A cherry 3 ins. diam. bears N. 25° E. 15 lks. dist. marked 1/4 & 1/32 S. B. T. Land mountainous & rolling & brushy. Soil 1st & 2nd rate. Grass. | |
| | From the 1/32 & 1/4 Sec. Corner in the center of Sec. 36. I run N. 1° 30' W. on true line in Sec 36 Var. 20° E. Descend. | |
| 4.75 | Fence N.E. & S. W. | |
| 10.00 | Set stone 10x8x6 ins. 7 ins. in the ground for 1/32 Sec. corner marked 1/32 on W. face, dug pits 18x18x12 ins. N. & S. of stone 5 1/2 ft. dist. And raised a mound of earth 1 1/2 ft. high 3 1/2 ft. base over it. Land rolling. Soil 1st rate. Some cultivated. | |