

Sub Subdivision of Township 3 North Range 35 East.

Chains.

79.42 To point of beginning.
Land mostly level.
Soil 1st rate.
Not improved.

East on random through S. $\frac{1}{2}$ of Sec. 11
Va. $20\frac{1}{2}^{\circ}$ East.
Commencing at 1/16 Sec. cor. 20 chains N. of S. W. cor.
of Sec. 14.

79.25 Set temp. cors. at 20, 40 and 60 chains. And at
Intersect E. bdy. 50 lks. S. of 1/16 Sec. cor. Thence
S. $89^{\circ} 39'$ West on true line.

3.25 Wagon road bears N. E.

19.81 Set basalt stone 14x8x8 ins. 10 ins. in the ground for
1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12
ins. E. & W. of stone $5\frac{1}{2}$ ft. dist. raised mound of earth
 $1\frac{1}{2}$ ft. high and $3\frac{1}{2}$ ft. base over it.

39.62 Set basalt stone 14x8x6 ins. 10 ins. in the ground for
1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12
ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of
earth $1\frac{1}{2}$ ft. high and $3\frac{1}{2}$ ft. base over it.

45.00 Ravine bears N. W.

59.43 Deposited charred stake 12 ins. in the ground for 1/16
Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$
ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base
over it. And in E. pit drove stake 2 ft. long 2 ins.
square 12 ins. in the ground marked 1/16 S. on N. face.

79.25 To point of beginning.
Land rolling.
Soil 1st rate.
Not cultivated.

East on random line through center of Sec. 14.
Va. 20° East.
Commencing at $\frac{1}{2}$ Sec. cor. bet. Secs. 14 & 15.

-50