

Sub Subdivision of Township 3 North Range 35 East

Chains	<p>Sec. cor. Dug pits 18x18x12 ins, E. &amp; W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground, marked 1/16 S. on N. face.</p>	
38.48	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>	
57.72	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft. dist. raised a mound of earth 1½ ft. high 3½ base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>	
76.96	<p>To point of beginning. Land rolling. Soil 1st rate.</p>	
East on random through S. ½ of Sec. 22.		
	Va. 21° East.	
	Commencing at 1/16 Sec. cor. 20 chains N. of S. W. cor. of Sec. 22.	
	Set temporary cors. at 20, 40 and 60 chains. And at	
76.80	Intersect E. bdy. 42 lks. S. of 1/16 Sec. cor. Thence S. 89° 42' W. on true line.	
15.00	Gulch bears S. W.	-100
19.20	Set basalt stone 10x10x10 ins. 6 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it.	
24.00	Gulch bears N. W.	-50
38.40	Set basalt stone 12x8x6 ins. 8 ins. in the ground for ¼ Sec. cor. marked ¼ on N. face. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. And raised mound of earth	