

Sub Sudivision of Township 3 North Range 35 East.

Chains 76.88	To point of beginning. Soil 1st rate. Land rolling.
	East on random through Center of Sec. 27. Va. 21° East. Commencing at $\frac{1}{4}$ Sec. cor. bet Secs. 27 & 28. Set temporary cors. 20, 40 and 60 chains. And at 76.92 Intersect E. bdy. 30 lks. S. of $\frac{1}{4}$ Sec. cor. Thence S. 89° 47' W. on true line
19.23	Set basalt stone 12x8x6 ins. 8 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stone 5 $\frac{1}{2}$ ft. dist. and raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And marked stone 1/16 on N. face.
38.46	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face
57.69	Set basalt stone 18x14x12 ins. 12 ins. in the ground for 1/16 Sec. cor. marked 1/16 S. on N. face. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. and raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it.
76.92	To point of beginning. Land slightly rolling. Soil 1st rate. Sept. 26, 1887
	East on random through N. $\frac{1}{16}$ of Sec. 27. Va. 21° East. Commencing at 1/16 Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor. bet. Secs. 27 & 28. Set temporary cors. at 20, 40 and 60 chains. And at 76.96 Intersect E. bdy. 35 lks. S. of 1/16 Sec. cor. Thence S. 89° 45' West on true line.
19.24	Deposited charred stake 12 ins. in the ground for 1/16